

Community Services Department  
Planning and Building  
**ADMINISTRATIVE PERMIT APPLICATION**



Community Services Department  
Planning and Building  
1001 E. Ninth St., Bldg. A  
Reno, NV 89512-2845

Telephone: 775.328.6100

## Washoe County Development Application

Your entire application is a public record. If you have a concern about releasing personal information, please contact Planning and Building staff at 775.328.6100.

<b>Project Information</b>		Staff Assigned Case No.: _____	
Project Name: <b>Lipscomb Garage</b>			
Project Description: Detached Garage			
Project Address: 195 E Sky Ranch Blvd			
Project Area (acres or square feet): 4000			
Project Location (with point of reference to major cross streets <b>AND</b> area locator): <b>E Sky Ranch Blvd and Omni Dr</b>			
Assessor's Parcel No.(s):	Parcel Acreage:	Assessor's Parcel No.(s):	Parcel Acreage:
534-113-02	1.002		
Indicate any previous Washoe County approvals associated with this application: Case No.(s). N/A			
<b>Applicant Information</b> (attach additional sheets if necessary)			
<b>Property Owner:</b>		<b>Professional Consultant:</b>	
Name: Aaron Lipscomb		Name: Element Engineering	
Address: 195 E Sky Ranch Blvd		Address: 3960 Glenview Terr	
Sparks, NV	Zip: 89441	Reno, NV	Zip: 89503
Phone: 775-686-0310	Fax:	Phone: 775-762-5461	Fax:
Email: bdnatalied@gmail.com		Email: andrew@elementengineer.com	
Cell: 775-686-0310	Other: mobile	Cell:	Other:
Contact Person: Natalie Davidson		Contact Person: Natalie Davidson	
<b>Applicant/Developer:</b>		<b>Other Persons to be Contacted:</b>	
Name:		Name: Natalie Davidson	
Address:		Address: 195 E Sky Ranch Blvd	
	Zip:	Sparks, NV	Zip: 89441
Phone:	Fax:	Phone: 775-686-0310	Fax:
Email:		Email: bdnatalied@gmail.com	
Cell:	Other:	Cell:	Other:
Contact Person:		Contact Person: Natalie Davidson	
<b>For Office Use Only</b>			
Date Received:	Initial:	Planning Area:	
County Commission District:		Master Plan Designation(s):	
CAB(s):		Regulatory Zoning(s):	

**Administrative Permit Application  
Supplemental Information**  
(All required information may be separately attached)

1. What is the type of project or use being requested?

**Detached Garage**

2. What section of the Washoe County code requires the Administrative permit required?

**110.306**

3. What currently developed portions of the property or existing structures are going to be used with this permit?

**N/A**

4. What improvements (e.g. new structures, roadway improvements, utilities, sanitation, water supply, drainage, parking, signs, etc.) will have to be constructed or installed and what is the projected time frame for the completion of each?

**N/A**

5. Is there a phasing schedule for the construction and completion of the project?

**Construction to begin as soon as permits are approved**

6. What physical characteristics of your location and/or premises are especially suited to deal with the impacts and the intensity of your proposed use?

**the garage will decrease weeds on the property and remove vehicles and trailers f**

7. What are the anticipated beneficial aspects or effect your project will have on adjacent properties and the community?

**The Property will not have vehicles visible, add wind break to neighboring property**

8. What will you do to minimize the anticipated negative impacts or effect your project will have on adjacent properties?

**Keep construction to daytime hours to not disturb neighbors**

9. Please describe any operational parameters and/or voluntary conditions of approval to be imposed on the administrative permit to address community impacts.

**N?A**

10. How many improved parking spaces, both on-site and off-site, are available or will be provided? (Please indicate on site plan.)

There will be indoor parking on this facility

11. What types of landscaping (e.g. shrubs, trees, fencing, painting scheme, etc.) are proposed? (Please indicate location on site plan.)

natural/ groomed landscaping

12. What type of signs and lighting will be provided? On a separate sheet, show a depiction (height, width, construction materials, colors, illumination methods, lighting intensity, base landscaping, etc.) of each sign and the typical lighting standards. (Please indicate location of signs and lights on site plan.)

N?A

13. Are there any restrictive covenants, recorded conditions, or deed restrictions (CC&Rs) that apply to the area subject to the administrative permit request? (If so, please attach a copy.)

Yes  No

14. Utilities:

a. Sewer Service	Septic Tank
b. Water Service	Great Basin Water Company

For most uses, the Washoe County Code, Chapter 110, Article 422, Water and Sewer Resource Requirements, requires the dedication of water rights to Washoe County. Please indicate the type and quantity of water rights you have available should dedication be required:

c. Permit #	N/A	acre-feet per year	N/A
d. Certificate #	N/A	acre-feet per year	N/A
e. Surface Claim #	N/A	acre-feet per year	N/A
f. Other, #	N/A	acre-feet per year	N/A

Title of those rights (as filed with the State Engineer in the Division of Water Resources of the Department of Conservation and Natural Resources):

unknown

# Administrative Permit Application Supplemental Information for Care of the Infirm

(All required information, to include the physician's signed affidavit, is considered a public record and will be treated as such by Washoe County. Information may be attached separately)

1. Name of the Infirm:

Detached Garage

2. Name of Nevada licensed physician identifying the need for on-premise care and the physician's estimate as to the length of on-premise care required (attach physician's signed affidavit, form on page 11):

110.306

3. Name(s) of the Caregiver(s):

N/A

4. Describe the type and size of recreational vehicle or self-contained travel trailer that is proposed for use as a temporary residence of the caregiver. (Attach a site map showing the proposed location.)

N/A

5. Describe the arrangements/methods proposed for the temporary provision of:

a. Water Service:

Great Basin Water Service

b. Sewage (Sanitary Sewer) Service:

Septic Tank

c. Garbage (Solid Waste) Service:

Waste Management

d. Electricity:

NV Energy

e. Natural Gas:

NV Energy

6. What will you do to minimize the anticipated negative impacts or effect your waiver will have on adjacent properties?

Keep construction to daytime hours to not disturb neighbors

7. What types of landscaping (e.g. shrubs, trees, fencing, painting scheme, etc.) are proposed? (Please indicate location on site plan.)



natural/ groomed landscaping

8. Are there any restrictive covenants, recorded conditions, or deed restrictions (CC&Rs) that apply to the area subject to the administrative permit request? (If so, please attach a copy.)

<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No
------------------------------	--

9. Community Services (provided and nearest facility):

a. Fire Station	Truckee Meadows Fire Department
b. Health Care Facility	Northern Nevada Medical Center
c. Elementary School	Spanish Springs Elementary
d. Middle School	Shaw Middle
e. High School	Spanish Springs
f. Parks	Eagle Canyon
g. Library	Spanish Springs Library
h. Citifare Bus Stop	N/A



REGULATORY ZONE DEVELOPMENT STANDARDS							
Regulatory Zone	Title	Front (feet)	Yards - Setbacks	Rear (feet)	Maximum Height (feet)	Minimum Density (Sublot)	Minimum Lot Area (sq. feet)
LDR	Low Density Rural	30	30	30	35	0.3	200
MDR	Medium Density Rural	30	15	30	35	0.2	300
HDR	High Density Rural	30	15	30	35	0.4	100
LDS	Low Density Suburban	30	12	30	35	1	35,000 sf

**SITE SURVEY NOTES**

1. ALL WORK PERFORMED ON THIS PROJECT SHALL BE IN CONFORMANCE WITH THESE PLANS AND THE STANDARDS SET BY THE LOCAL BUILDING OFFICIAL.
2. NO DEVIATION FROM THESE DRAWINGS SHALL BE MADE WITHOUT PRIOR DOCUMENTED CONSENT OF THE LAND SURVEYOR. REPORT ANY PLAN DISCREPANCIES TO THE LAND SURVEYOR AND OWNER.
3. ALL DIMENSIONS SHALL BE VERIFIED ON PLANS AND DIMENSIONS SHALL BE VERIFIED WITHIN THE PROJECT PRIOR TO COMMENCEMENT OF WORK. DO NOT SCALE DRAWINGS, WRITTEN DIMENSIONS PREVAIL.

**SITE SURVEY LEGEND**

- KEY**
- DESCRIPTION
  - FOUND CAP
  - PROPERTY CORNER
- \* ED = DISTING, (F) = PROPOSED, CONC = CONCRETE, CH = OVERHANG  
 (F) = FUTURE, CONT. = CONTINUATION, SB = SETBACK, HP = HIGH POINT  
 (UG) = UNDERGROUND



DATE: \_\_\_\_\_

REVISIONS:




A SITE SURVEY FOR:  
**195 E SKY RANCH BLVD**  
 SPARKS, NV 89441  
 APN: 534-113-02

SCALE: 1" = 20'  
 DRAWN: AMH  
 CHECKED: AMH  
 DATE: 8/24/23  
 NOTES:

SHEET  
**SS**

SITE SURVEY  
 SCALE: 1" = 20'





PAD FOOTING CALCULATION

**Footings / Foundation Design** 1-15  
2018 IBC references ACI 318-14



**Project Information:**


Risk Category:	II
Site Class:	D
Maximum Dead Reaction:	2800 lbs
Maximum Live Reaction:	9900 lbs

Resp. Mod. Factor (R):	-
Importance Factor (I):	1.00

ASD Factor:	0.7
-------------	-----

**Effective Seismic Weights (W):**

Dead:	2800 lbs
Live:	9900 lbs
Total:	12700 lbs



$FND_{sp} = (P_u + W_u) / S_u$

**Concrete Foundation Weight, W<sub>c</sub>:**

Width (sq. ft):	3.0
Conc. Unit W:	150 pcf
Depth, A:	3.00 ft
Total (W):	16750 lbs


**Required Foundation Size (square):**

Width <sub>required</sub>	<	Width <sub>provided</sub>
2.9	<	3.0

**True, Footing Size OK**

**Req. Rebar Specs:**

Top: #4 @ 8" OC, EW Bar, (2" Clr)  
Bot: #4 @ 8" OC, EW Bar, (2" Clr)  
Vert: #4 @ 8" OC, ES Bar, (2" Clr)



**PAD FOOTING SECTION**  
SCALE: 1" = 1'

**FOUNDATION PLAN NOTES**

- ALL WORK PERFORMED ON THIS PROJECT SHALL BE IN CONFORMANCE WITH THESE PLANS AND THE STANDARDS SET BY THE LOCAL BUILDING OFFICIAL.
- NO DEVIATION FROM THESE DRAWINGS SHALL BE MADE WITHOUT PRIOR DOCUMENTED CONSENT OF THE BUILDER. REPORT ANY PLAN DISCREPANCIES TO ENGINEER AND OWNER.
- SLOPE ADJACENT SOIL AWAY FROM STRUCTURE AT 5% MINIMUM FOR 10'. RAIN DOWNSPOUTS SHALL BE INSTALLED TO ROUTE STORM RUNOFF INTO CONSTRUCTED SWALES AND INTO PERCOLATION BASINS.

**PLAN INFORMATION**

KEY	DESCRIPTION
●	NOT USED
○	NOT USED

\* (E) = EXISTING, (P) = PROPOSED, (H) = HIGH POINT, (T) = TURN POINT  
LW = LOW POINT, EW = EACH WAY, OC = ON CENTER

**RIGID FRAME: BASIC COLUMN REACTIONS (k)**

Frame Line	Column Line	Dead		Collateral		Live		Snow		Wind_Left1		Wind_Right1	
		Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert
2*	E	0.6	1.6	0.7	1.5	2.9	6.0	6.7	14.0	-5.7	-8.4	0.5	-3.4
2*	A	-0.6	1.6	-0.7	1.5	-2.9	6.0	-6.7	14.0	0.5	-3.4	5.7	-3.4

Frame Line	Column Line	Wind_Left2		Wind_Right2		Wind_Long1		Wind_Long2		Seismic_Left		Seismic_Right	
		Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert
2*	E	-5.7	-5.1	0.4	-2.0	-0.6	-9.8	-1.3	-8.8	-1.8	-1.1	1.8	1.1
2*	A	-0.4	-2.0	5.7	-5.1	1.3	-8.8	0.6	-9.8	-1.8	1.1	1.8	-1.1

Frame Line	Column Line	Seismic_Long		MIN_SNOW		F1UNB_SL_L		F1UNB_SL_R	
		Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert
2*	E	0.0	-5.6	6.7	14.0	5.6	13.6	5.6	8.0
2*	A	0.0	-5.6	-6.7	14.0	-5.6	8.0	-5.6	13.6

**ENDWALL COLUMN: BASIC COLUMN REACTIONS (k)**

Frm Line	Col Line	Dead		Live		Snow		Wind_Left1		Wind_Right1		Wind_Left2		Wind_Right2		Wind Press
		Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert			
1	E	0.2	0.2	1.1	1.6	-1.8	-3.4	0.0	1.7	-1.6	-2.5	0.0	1.9	0.0	0.0	
1	D	0.7	0.6	-4.0	5.6	0.0	-1.3	1.8	-5.0	0.0	0.7	1.6	-3.7	-2.5	0.0	
1	B	0.6	0.6	4.0	5.6	0.0	-2.1	0.0	-3.7	0.0	-1.2	0.0	-2.8	-2.5	0.0	
1	A	0.2	0.2	1.1	1.6	0.0	-1.2	0.0	-0.9	0.0	-0.6	0.0	-0.4	0.0	0.0	


Frm Line	Col Line	Wind		Wind_Long1		Wind_Long2		Seis_Left		Seis_Right		Seis_Long		MIN_SNOW	
		Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert
1	E	0.0	0.0	-0.7	-0.5	-1.6	-2.5	-3.1	0.0	3.8	0.0	0.0	0.0	1.6	0.0
1	D	2.7	0.5	-3.9	0.0	-1.3	0.0	3.1	2.5	-3.7	0.2	0.0	5.6	0.0	
1	B	2.7	0.0	-2.0	0.0	-3.1	0.0	0.2	0.0	-0.2	0.2	0.0	5.6	0.0	
1	A	0.0	0.0	-0.9	0.0	-1.5	0.0	-0.2	0.0	0.2	0.0	0.0	1.6	0.0	

Frm Line	Col Line	E1UNB_SL_L		E1UNB_SL_R	
		Horiz	Vert	Horiz	Vert
1	D	0.0	6.5	0.0	2.6
1	B	0.0	2.9	0.0	6.6
1	A	0.0	0.3	0.0	1.5

Frm Line	Col Line	Dead		Live		Snow		Wind_Left1		Wind_Right1		Wind_Left2		Wind_Right2		Wind Press
		Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert			
5	A	0.4	0.3	1.9	2.7	0.0	-1.8	0.0	-1.5	0.0	-1.1	0.0	-0.7	0.0	0.0	
5	C	1.1	1.0	5.9	8.7	-1.8	-6.5	0.0	-3.0	-1.6	-4.8	0.0	-1.7	-4.0	0.0	
5	E	0.4	0.3	1.9	2.7	0.0	0.5	1.8	-3.4	0.0	1.0	1.6	-2.5	0.0	0.0	

Frm Line	Col Line	Wind		Wind_Long1		Wind_Long2		Seis_Left		Seis_Right		Seis_Long		MIN_SNOW	
		Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert
5	A	0.0	0.0	-2.3	0.0	-1.2	0.0	0.2	0.0	-0.2	0.0	0.0	2.7	0.0	
5	C	4.3	0.0	-3.6	-5.5	4.6	-2.5	2.7	0.0	-2.1	0.3	0.0	8.7	0.0	
5	E	0.0	0.5	-1.6	0.0	-1.7	0.0	2.6	2.5	-1.9	0.0	0.0	2.7	0.0	

Frm Line	Col Line	E2UNB_SL_L		E2UNB_SL_R		E2PAT_LL_1		E2PAT_LL_2	
		Horiz	Vert	Horiz	Vert	Horiz	Vert	Horiz	Vert
5	A	0.0	3.3	0.0	0.4	0.0	2.2	0.0	-0.3
5	C	0.0	7.3	0.0	7.3	0.0	0.0	0.0	3.0
5	E	0.0	0.4	0.0	3.3	0.0	-0.3	0.0	2.2



**FOUNDATION PLAN**  
SCALE: 1" = 7'



REVISIONS:

DATE:	
REVISION:	



**ELEMENT ENGINEERING**  
775-962-2462  
775-962-2462  
info@elementeng.com

A FOUNDATION PLAN FOR THE:  
**DAVIDSON SHOP**  
195 E SKY RANCH BLVD  
SPARKS, NV 89441 | APN: 534-113-02

SCALE: VARIES  
DRAWN: AMH  
CHECKED: AMH  
DATE: 8/28/23  
NOTES:

SHEET  
**FP**

**BUILDER/CONTRACTOR RESPONSIBILITIES**

**Drawing Validity** – These drawings, supporting structural calculations and design certification are based on the order documents as of the date of these drawings. These documents describe the material supplied by the manufacturer as of the date of these drawings. Any changes to the order documents after the date on these drawings may void these drawings, supporting structural calculations and design certification. The Builder/Contractor is responsible for notifying the building authority of all changes to the order documents which result in changes to the drawings, supporting structural calculations and design certification.

**Builder Acceptance of Drawings** – Approval of the manufacturer's drawings and design data affirms that the manufacturer has correctly interpreted and applied the requirements of the order documents and constitutes Builder/Contractor acceptance of the manufacturer's interpretations of the order documents and standard product specifications, including its design, fabrication and quality criteria standards and tolerances. (AISC code of standard practice APR 10 Section 4.4.1)

**Code Official Approval** – It is the responsibility of the Builder/Contractor to ensure that all project plans and specifications comply with the applicable requirements of any governing building authority. The Builder/Contractor is responsible for securing all required approvals and permits from the appropriate agency as required.

**Builder is responsible for State, Federal and OSHA safety compliance** – The Builder/Contractor is responsible for applying and observing all pertinent safety rules and regulations and OSHA standards as applicable.

**Building Erection** – The Builder/Contractor is responsible for all erection of the steel and associated work in compliance with the Metal Building Manufacturers drawings. Temporary supports, such as temporary guys, braces, false work or other elements required for erection will be determined, furnished and installed by the erector. (AISC Code of Standard Practice APR 10 Section 7.10.3)

**Discrepancies** – Where discrepancies exist between the Metal Building plans and plans for other trades, the Metal Building plans will govern. (AISC Code of Standard Practice APR 10 Section 3.3)

**Materials by Others** – All interface and compatibility of any materials not furnished by the manufacturer are the responsibility of and to be coordinated by the Builder/Contractor or A/E firm. Unless specific design criteria concerning any interface between materials if furnished as a part of the order documents, the manufacturer's assumptions will govern.

**Modification of the Metal Building from Plans** – The Metal Building supplied by the manufacturer has been designed according to the Building Code and specifications and the loads shown on this drawing. Modification of the building configuration, such as removing wall panels or braces, from that shown on these plans could affect the structural integrity of the building. The Metal Building Manufacturer or a Licensed Structural Engineer should be consulted prior to making any changes to the building configuration shown on these drawings. The Metal Building Manufacturer will assume no responsibility for any loads applied to the building not indicated on these drawings.

**Foundation Design** – The Metal Building Manufacturer is not responsible for the design, materials and workmanship of the foundation. Anchor rod plans prepared by the manufacturer are intended to show only location, diameter and projection of the anchor rods required to attach the Metal Building System to the foundation. It is the responsibility of the end customer to ensure that adequate provisions are made for specifying rod embedment, bearing values, tie rods and or other associated items embedded in the concrete foundation, as well as foundation design for the loads imposed by the Metal Building System, other imposed loads, and the bearing capacity of the soil and other conditions of the building site. (MBMA MBMS Chapter 4 Section 3.2.2 and Section A3)

**Shimming** – In accordance with Section 6.10 of Chapter 4, Common Industry Practices in the Metal Building Systems Manual, shimming is a normal part of erection and is not subject to claim.

**PROJECT NOTES**

Material properties of steel bar, plate, and sheet used in the fabrication of built-up structural framing members conform to ASTM A529, ASTM A572, or ASTM A1011 with 55 ksi min. yield, except flanges wider than 12" and thicker than 3/8", all flanges thicker than 1", and all webs thicker than 3/8" are 50 ksi min. yield. Rod X-bracing conforms to ASTM A529 or ASTM A572 with 50 ksi min. yield. Cable X-bracing conforms to ASTM A475 7 Strand Extra High-Strength grade. Hot rolled structural shapes conform to ASTM A992, ASTM A529, or ASTM A572 with 50 ksi min. yield. Hot rolled angles other than flange braces, conform to ASTM A36 minimum. Round and rectangular HSS conforms to ASTM A500 Grade B. Cold-formed steel secondary framing Members conform to ASTM A1011 or ASTM A653 Grade 55 with 55 ksi min. yield.

The manufacturer does not assume any responsibility for the erection nor field supervision of the structure and or any special inspections that may be required by the local building authority during erection (including inspection of the high strength bolts or field welds) as required during erection. The coordination and the costs associated for setting up and Special Inspections are the responsibility of the Erector, Owner, Architect, or Engineer of Record.

Design is based upon the more severe loading of either the roof snow load or the roof live load.

Loads, as noted, are given within order documents and are applied in general accordance with the applicable provisions of the model code and/or specification indicated. Neither the manufacturer nor the certifying engineer declares or attests that the loads as designated are proper for the local provisions that may apply or for site specific parameters. The manufacturer's Engineer's certification is limited to design loads supplied by an Architect and/or engineer of record for the overall construction project.

This project is designed using manufacturer's standard serviceability standards. Generally this means that all stresses and deflections are within typical performance limits for normal occupancy and standard metal building products. If special requirements for deflections and vibrations must be adhered to, then they must be clearly stated in the contract documents.

This metal building system is designed as enclosed. All exterior components (i.e. doors, windows, vents, etc.) must be designed to withstand the specified wind loading for the design of components and cladding in accordance with the specified building code. Doors are to be closed when a maximum of 50% of design wind velocity is reached.

Unless otherwise noted, special inspection of fabricated items is not required. Per IBC section 1704.2.5.1, The fabricator is approved to perform such work without special inspection through maintenance of IAS AC 472 certification MB-135

**BO-T TIGHTENING**—Bolted joints with ASTM A325 type 1 bolts greater than 1/2" diameter are specified as pretensioned joints in accordance with the most recent edition of the RCSC Specification for Structural Joints Using ASTM A325 or A490 Bolts. Pretensioning can be accomplished by using the turn-of-nut method of tightening, calibrated wrench/twist-off-type tension-control bolts or direct-tension-indicator as acceptable to the Inspecting Agency and Building Official. Installation inspection requirements for pretensioned joints (Specification for Structural Joints Section 9.2) using turn-of-nut method is suggested. The connections on this project are not slip critical.

The metal building manufacturer has not designed the structure for snow accumulation loads at the ground level which may impose snow loads on the wall framing provided by the manufacturer.

The design collateral load has been uniformly applied to the design of the building. Hanging loads are to be attached to the purlin web. This may not be appropriate for heavily concentrated loads. Any attached load in excess of 150 pounds shall be accounted for by special design performed by a licensed engineer using concentrated loads and may require separate support members within the roof system.

**ENGINEERING DESIGN CRITERIA**

Building Code.....	IBC 18
Building Risk Category.....	II – Normal
Roof Dead Load	
Superimposed.....	1.920 psf
Collateral.....	3 psf
Roof Live Load.....	20.00 psf Yes reduction
Snow	
Ground Snow Load (Pg).....	40.00 psf
Snow Load Importance Factor (I <sub>s</sub> )	1.00
Snow Exposure Factor (C <sub>e</sub> ).....	1.00
Thermal Factor (C <sub>t</sub> ).....	1.00
Flat Roof Snow Load (P <sub>f</sub> ).....	28.00 psf
Minimum Roof Snow Load (P <sub>m</sub> ).....	28.00 psf

Wind	
Ultimate Wind Speed (V <sub>ult</sub> ).....	120 mph
Nominal Wind Speed (V <sub>asd</sub> ).....	93 mph (IBC Section 1609.3.1)
Serviceability Wind Speed.....	68 mph
Ground Elevation Factor.....	0.85 (4526.001 ASL)
Wind Exposure Category.....	B
Internal Pressure Coefficient (GC <sub>pi</sub> ) 0.18 / -0.18	
Loads for components not provided by building manufacturer	
Wall Edge Zones (within 5.00' of corner)	
19.18 psf pressure	
-25.69 psf suction	
Other Wall Zones 19.18 psf pressure	
-20.81 psf suction	

These values are the maximum values required based on a 10 square foot area. Components with larger areas may have lower wind loads. Zones per ASCE 7-16; FIG. 30.3-1 Zones pressures shown are Un-Factored

Seismic	
Seismic Importance Factor (I <sub>e</sub> ).....	1.00
Seismic Design Category.....	D
Soil Site Class.....	d
S <sub>1</sub> .....	1.416 g
S <sub>2</sub> .....	1.132 g
S <sub>3</sub> .....	0.476 g
S <sub>d1</sub> .....	0.579 g
Analysis Procedure.....	Equivalent Lateral Force
Location.....	Int RF Front SW Back SW Left SW Right EW
C <sub>4</sub>	B3
B <sub>3</sub>	B3
L <sub>5</sub>	B3
R.....	3.25 3.25 3.25 3.25 3.25 3.25
C <sub>s</sub> .....	0.349 0.349 0.349 0.349 0.349

Design Base Shear in kips (V) Transverse 12.02  
Design Base Shear in kips (V) Longitudinal 12.10

Basic Structural System (from ASCE 7-16 Table 12.2-1)  
System – Basic Force Resisting System  
H – Steel System not Specifically Detailed for Seismic Resistance  
C4 – Steel Ordinary Moment Frames  
B3 – Steel Ordinary Concentric Braced Frames  
G2 – Steel Ordinary Cantilevered Column Systems  
R – Response Modification Coefficient  
C<sub>s</sub> – Seismic Response Coefficient  
Transverse – Direction Parallel to the Rigid Frames  
Longitudinal – Direction Perpendicular to the Rigid Frames

BEJUN ANKLESARIA, PE SE  
2918 CREEK TERRACE DR.  
MISSOURI CITY TX 77459  
281-499-1472

Building Descriptions				
Building ID	Width(ft)	Length(ft)	Height(ft)	Slope
Building A	50	80	16	3.0:12

Drawing Index	
Page	Description
C1	COVER SHEET
F1	ANCHOR BOLT PLAN
F2	ANCHOR BOLT REACTIONS
F3	ANCHOR BOLT DETAILS
E1	ROOF FRAMING PLAN
E2	ROOF SHEETING PLAN
E3	FRONT SIDEWALL
E4	BACK SIDEWALL
E5	LEFT ENDWALL
E6	RIGHT ENDWALL
E7	FRAME CROSS SECTION
DET1-24	STANDARD DETAILS
R1-R3	INSTALLATION SHEETS

**DRAWING STATUS**

FOR APPROVAL  
These drawings, being For Approval, are by definition not final, and are for conceptual representation only. Their purpose is to confirm proper interpretation of the project documents. Only drawings issued "For Erector Installation" can be considered as complete.


FOR CONSTRUCTION PERMIT  
These drawings, being for Permit, are by definition not final. Only drawings issued "For Erector Installation" can be considered as complete.

FOR ERECTOR INSTALLATION  
Final drawings for construction.

For questions or assistance Concerning Erection call:  
**252-977-2131**  
Monday-Friday 7:30am to 5:00pm

**ENGINEERING SEAL**


The engineer whose seal appears hereon is an employee for the manufacturer for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project.



Download panel installation manuals from:  
[www.cornerstonebuildingbrands.com/installationmanuals/](http://www.cornerstonebuildingbrands.com/installationmanuals/)

Descargue los manuales de instalación del panel desde:  
[www.cornerstonebuildingbrands.com/installationmanuals/](http://www.cornerstonebuildingbrands.com/installationmanuals/)

1/2"Ø A325 BOLT GRIP TABLE (UNLESS NOTED)			
GRIP	LENGTH	BOLT LENGTH	NOTE:
0 TO 9/16"	1 1/4" F.T.		FULL THREAD ENGAGEMENT IS DEEMED TO HAVE BEEN MET WHEN THE END OF THE BOLT IS FLUSH WITH THE FACE OF THE NUT.
Over 9/16" TO 1 1/16"	1 3/4" F.T.		
Over 1 1/16" TO 1 5/16"	2"		
Over 1 5/16" TO 1 9/16"	2 1/4"		
Over 1 9/16" TO 1 13/16"	2 1/2"		
Over 1 13/16" TO 2 1/16"	2 3/4"		
LOCATIONS OF BOLTS LONGER THAN 2 3/4" NOTED ON ERECTION DRAWINGS			
F.T. DENOTES FULLY THREADED			




ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV



PROJECT:	NATALIE DAVIDSON						
CUSTOMER:	THE STEEL BUILDER	OWNER: NATALIE DAVIDSON					
LOCATION:	SPARKS, NV 89441-8549 US						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/3/23	N.T.S.	1	A	19-B-27926	C1	0

Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 385-8001  
Rocky Mount, NC. (252) 977-2131  
[www.cscobuildings.com](http://www.cscobuildings.com)

○ Dia= 5/8"  
 ✖ Dia= 3/4"




ANCHOR BOLT PLAN

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV



Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 385-8001  
 Rocky Mount, NC. (252) 977-2131  
 www.cecobuildings.com

PROJECT:	NATALIE DAVIDSON						
CUSTOMER:	THE STEEL BUILDER			OWNER:	NATALIE DAVIDSON		
LOCATION:	SPARKS,NV 89441-8549 US						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	F1	0



Drawing has been digitally signed.

**GENERAL NOTES**

- THE REACTIONS PROVIDED ARE BASED ON THE ORDER DOCUMENTS AT THE TIME OF MAILING. ANY CHANGES TO BUILDING LOADS OR DIMENSIONS MAY CHANGE THE REACTIONS. THE REACTIONS WILL BE SUPERSEDED AND VOIDED BY ANY FUTURE MAILING.
- THE REACTIONS PROVIDED HAVE BEEN CREATED WITH THE FOLLOWING LAYOUT (UNLESS NOTED OTHERWISE)
  - A REACTION TABLE IS PROVIDED WITH REACTIONS FOR EACH LOAD GROUP
  - RIGID FRAMES
    - SEE NOTE 3.
  - ENDWALLS
    - SEE NOTE 3.
  - X-BRACING
    - X-BRACING REACTIONS ARE INCLUDED IN VALUES SHOWN IN THE REACTION TABLES AS NOTED IN THE BRACING REACTIONS TABLE.
    - FOR IBC AND UBC BASED BUILDING CODES, WHEN X-BRACING IS PRESENT IN THE SIDEWALL, INDIVIDUAL LONGITUDINAL SEISMIC LOADS DO NOT INCLUDE THE AMPLIFICATION FACTOR,  $\Omega_{M2}$ .
    - FOR IBC AND UBC BASED BUILDING CODES, WHEN X-BRACING IS PRESENT IN THE ENDWALL, INDIVIDUAL TRANSVERSE SEISMIC LOADS DO NOT INCLUDE THE AMPLIFICATION FACTOR,  $\Omega_{M2}$ .
- THE METAL BUILDING MANUFACTURER IS RESPONSIBLE ONLY FOR THE PORTION OF THE ANCHOR ROD DESIGN PERTAINING TO THE TRANSFER OF FORCES BETWEEN THE BASE PLATE BEARING AND THE ANCHOR RODS SHEAR AND TENSION. THE METAL BUILDING MANUFACTURER IS NOT RESPONSIBLE FOR THE ANCHOR ROD EMBEDMENT FOR TRANSFER OF FORCES TO THE FOUNDATION. THE METAL BUILDING MANUFACTURER DOES NOT DESIGN AND IS NOT RESPONSIBLE FOR THE DESIGN, MATERIAL, AND CONSTRUCTION OF THE FOUNDATION EMBEDMENT. THE END USER CUSTOMER SHALL ASSURE THAT ADEQUATE PROVISIONS ARE MADE TO THE FOUNDATION DESIGN FOR LOADS IMPOSED BY COLUMN REACTIONS OF THE BUILDINGS, OTHER IMPOSED LOADS, AND BEARING CAPACITY OF THE SOIL AND OTHER CONDITIONS OF THE BUILDING SITE. IT IS RECOMMENDED THAT THE ANCHORAGE AND FOUNDATION OF THE BUILDING BE DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER COMPETENT IN THE DESIGN OF SUCH STRUCTURES.
  - (REF. APPENDIX A3 OF THE MBMA METAL BUILDING SYSTEMS MANUAL)
- ANCHOR RODS ARE ASTM F1554 GR. 36 MATERIAL UNLESS NOTED OTHERWISE ON THE ANCHOR ROD LAYOUT DRAWING.
- REACTIONS ARE PROVIDED AS UN-FACTORED FOR EACH LOAD GROUP APPLIED TO THE COLUMN. THE FACTORS APPLIED TO LOAD GROUPS FOR THE STEEL COLUMN DESIGN MAY BE DIFFERENT THAN THE FACTORS USED IN THE FOUNDATION DESIGN. THE FOUNDATION ENGINEER SHALL APPLY THE APPROPRIATE LOAD FACTORS AND COMBINE THE REACTIONS IN ACCORDANCE WITH THE BUILDING CODE AND DESIGN SPECIFICATIONS FOR PROPER FOUNDATION DESIGN.
  - FOR PROJECTS USING ULTIMATE DESIGN WIND SPEEDS SUCH AS 2012 IBC, 2015 IBC, OR FLORIDA BUILDING CODE, THE WIND LOAD REACTIONS ARE AT A STRENGTH VALUE WITH A LOAD FACTOR OF 1.0.
  - FOR IBC CODES, THE SEISMIC REACTIONS PROVIDED ARE AT A STRENGTH LEVEL WITH A LOAD FACTOR OF 1.0, AND DO NOT CONTAIN THE RFD FACTOR.

THE MANUFACTURER DOES NOT PROVIDE "MAXIMUM" LOAD COMBINATION REACTIONS. HOWEVER, THE INDIVIDUAL LOAD REACTIONS PROVIDED MAY BE USED BY THE FOUNDATION ENGINEER TO DETERMINE THE APPLICABLE LOAD COMBINATIONS FOR HIS/HER DESIGN PROCEDURES AND ALLOW FOR AN ECONOMICAL FOUNDATION DESIGN.

**BUILDING BRACING REACTIONS**

Wall Loc	Col Line	E.D	Reactions in plane of wall ± Reactions(k)				Panel_Shear (lb/ft)
			Wind Horz	Seismic Vert	Wind Vert	Seismic Horz	
L_EW	1	E,D	Bracing, see EW reactions				
F_SW	A	2,3	3.8	7.9			
R_EW	5	C,E	Bracing, see EW reactions				
B_SW	E	3,2	3.8	7.9			

\*See RF reactions table for vertical and horizontal reactions in plane of the rigid frame.

**ENDWALL COLUMN:**

Frm Line		Col Line		Dead		Collat		Live		Snow		Wind_Left1		Wind_Right1		Wind_Left2		Wind_Right2		Wind Press	
Line	Line	Vert	Vert	Vert	Vert	Vert	Vert	Vert	Vert	Vert	Vert	Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert
1	D	0.2	0.2	1.1	1.6	-1.8	-3.4	0.0	1.7	-1.6	-2.5	0.0	1.9	0.0	1.9	0.0	0.0	0.0	0.0	0.0	0.0
1	D	0.7	0.6	4.0	5.6	0.0	-1.3	1.8	-5.0	0.0	-0.7	1.6	-3.7	-2.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1	B	0.6	0.6	4.0	5.6	0.0	-2.1	0.0	-3.7	0.0	-1.2	0.0	-2.8	-2.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1	A	0.2	0.2	1.1	1.6	0.0	-1.2	0.0	-0.9	0.0	-0.6	0.0	-0.4	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

Frm Line	Col Line	Wind Suct	Wind_Long1 Horz	Wind_Long2 Vert	Seis_Left Horz	Seis_Right Vert	Seis_Long Horz	-MNL_SNOW--
1	E	0.0	0.0	-0.7	-0.5	-1.6	-2.5	3.1
1	D	2.7	0.5	-3.9	0.0	-1.3	0.0	3.1
1	B	2.7	0.0	-2.0	0.0	-3.1	0.0	2.2
1	A	0.0	0.0	-0.9	0.0	-1.5	0.0	-0.2

Frm Line	Col Line	E1UNB_SL_L--	E1UNB_SL_R--	E2UNB_SL_L--	E2UNB_SL_R--	E2PAT_LL_1--	E2PAT_LL_2--
1	E	0.0	1.5	0.0	0.3		
1	D	0.0	6.6	0.0	2.6		
1	B	0.0	2.6	0.0	6.6		
1	A	0.0	0.3	0.0	1.5		

Frm Line	Col Line	Dead	Collat	Live	Snow	Wind_Left1	Wind_Right1	Wind_Left2	Wind_Right2	Wind Press
5	A	0.4	0.3	1.9	2.7	0.0	-1.8	0.0	-1.5	0.0
5	C	1.1	1.0	5.9	8.7	-1.8	-6.5	0.0	0.0	-1.7
5	E	0.4	0.3	1.9	2.7	0.0	0.5	1.8	-3.4	0.0

Frm Line	Col Line	Wind Suct	Wind_Long1 Horz	Wind_Long2 Vert	Seis_Left Horz	Seis_Right Vert	Seis_Long Horz	-MNL_SNOW--
5	A	0.0	0.0	-2.3	0.0	-1.2	0.0	-0.2
5	C	4.3	0.0	-3.6	-0.5	-4.6	-2.5	2.7
5	E	0.0	0.5	-1.6	0.0	-1.7	0.0	2.6

Frm Line	Col Line	E2UNB_SL_L--	E2UNB_SL_R--	E2PAT_LL_1--	E2PAT_LL_2--
5	A	0.0	3.3	0.0	2.2
5	C	0.0	7.3	0.0	3.0
5	E	0.0	0.4	0.0	3.3


**NOTES FOR REACTIONS**

BUILDING REACTIONS ARE BASED ON THE FOLLOWING BUILDING DATA:

WIDTH (FT) = 50  
 LENGTH (FT) = 80  
 LEAVE HEIGHT (FT) = 16 / 16  
 ROOF SLOPE (deg/12) = 3.0/12  
 DEAD LOAD (psf) = 1,920  
 COLLATERAL LOAD (psf) = 3  
 ROOF LIVE LOAD (psf) = 20.00 (Reducible)  
 FRAME LIVE LOAD (psf) = 12  
 FLAT ROOF SNOW LOAD (psf) = 28  
 GROUND SNOW LOAD (psf) = 40.00  
 ULTIMATE WIND SPEED (MILES) = 120 mph  
 NOMINAL WIND SPEED (VASD) = 93 mph (IBC Section 1609.3.1)  
 WIND CODE = BC-18  
 EXPOSURE = B  
 CLOSED/OPEN = Closed  
 IMPORTANCE - WIND = 1.00  
 IMPORTANCE - SEISMIC = 1.00  
 SEISMIC ZONE = D

REACTION KEY:  
 Wind Left/Right 1 = (with +CC) Internal Pressure  
 Wind Left/Right 2 = (with -CC) Internal Pressure  
 Wind\_Long 1 = Wind Load Case B at Left EW  
 Wind\_Long 2 = Wind Load Case B at Right EW  
 E#UNB\_SL\_L = Endwall Unbalanced Snow Left  
 E#UNB\_SL\_R = Endwall Unbalanced Snow Right  
 F#UNB\_SL\_L = Rigid Frame Unbalanced Snow Left  
 F#UNB\_SL\_R = Rigid Frame Unbalanced Snow Right

**FRAME LINES:** 2 3 4



**RIGID FRAME: ANCHOR BOLTS & BASE PLATES**

Frm Line	Col Line	Anchor Bolt Qty	Anchor Bolt Dia	Base Plate (in) Width	Base Plate (in) Length	Thick	Grout (in)
2*	E	4	0.750	6.000	10.500	0.375	0.0
2*	A	4	0.750	6.000	10.500	0.375	0.0

2\* Frame lines: 2 3 4

**RIGID FRAME: BASIC COLUMN REACTIONS (k)**

Frame Line	Column Line	Dead	Collateral	Live	Snow	Wind_Left1	Wind_Right1	Wind_Left2	Wind_Right2	Seismic_Left	Seismic_Right
2*	E	0.6	1.6	0.7	1.5	2.9	6.0	6.7	14.0	-5.7	-8.4
2*	A	-0.6	1.6	-0.7	1.5	-2.9	6.0	-6.7	14.0	-0.5	-5.4

Frame Line	Column Line	Wind_Left2	Wind_Right2	Wind_Long1	Wind_Long2	Seismic_Left	Seismic_Right
2*	E	-5.7	-5.1	0.4	-2.0	-0.6	-9.8
2*	A	-0.4	-2.0	5.7	-5.1	1.3	-8.8

Frame Line	Column Line	Seismic_Long	-MNL_SNOW--	F1UNB_SL_L	F1UNB_SL_R
2*	A	0.0	-5.6	6.7	14.0
2*	A	0.0	-5.6	-6.7	14.0

2\* Frame lines: 2 3 4

**ENDWALL COLUMN: ANCHOR BOLTS & BASE PLATES**

Frm Line	Col Line	Anchor Bolt Qty	Anchor Bolt Dia	Base Plate (in) Width	Base Plate (in) Length	Thick	Grout (in)
1	E	2	0.625	7.000	8.000	0.250	0.0
1	B	4	0.625	6.000	8.000	0.375	0.0
1	B	2	0.625	7.000	8.000	0.250	0.0
1	A	2	0.625	7.000	8.000	0.250	0.0
5	A	2	0.625	7.000	12.000	0.250	0.0
5	C	2	0.625	7.000	12.000	0.250	0.0
5	E	2	0.625	7.000	12.000	0.250	0.0

**ANCHOR BOLT SUMMARY**

Qty	Locate	Dia (in)	Type	Proj (in)
4	Jamb	5/8"	F1554	2.00
16	Endwall	5/8"	F1554	2.00
24	Frame	3/4"	F1554	2.50

**FLOOR REACTION NOTE:**

FOR VERTICAL LOADS, UPWARD IS POSITIVE AND DOWNWARD IS NEGATIVE. FOR HORIZONTAL REACTIONS, TO THE RIGHT IS POSITIVE AND TO THE LEFT IS NEGATIVE. FOUNDATION LOADS ARE IN OPPOSITE DIRECTIONS.



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV



Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 385-8001  
 Rocky Mount, NC. (252) 977-2131  
 www.cecobuildings.com

PROJECT:	NATALIE DAVIDSON	OWNER:	NATALIE DAVIDSON				
CUSTOMER:	THE STEEL BUILDER						
LOCATION:	SPARKS,NV 89441-8549 US						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/3/23	N.T.S.	1	A	19-B-27926	F2	0





ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV



**CECO Building Systems**  
Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 335-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com

PROJECT: NATALIE DAVIDSON  
CUSTOMER: THE STEEL BUILDER OWNER: NATALIE DAVIDSON  
LOCATION: SPARKS, NV 89441-8549 US

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	F3	0



\*\* = SAME FLANGE




The large leg of the Zee must be alternated from top to bottom in order to nest the member correctly. A triangle has been added to the end of the Zee near the connection holes, that will point to the large leg of the member.

SPECIAL BOLTS					
ROOF PLAN					
ID	QUAN	TYPE	DIA	LENGTH	WASH
1	4	A325	1/2"	1 1/4"	0
2	2	A325	1/2"	1 1/4"	2

MEMBER TABLE		
ROOF PLAN		
MARK	PART	LENGTH
P-1	8X25Z16	23'-1 1/2"
P-2	8X25Z16	24'-7 1/2"
P-3	8X25Z16	24'-7 1/2"
P-4	8X25Z16	23'-1 1/2"
E-1	8ES3L14	19'-11 1/2"
E-2	8ES3L14	19'-11 1/2"
E-3	8ES3L14	19'-11 1/2"
E-4	8ES3L14	19'-11 1/2"
E-5	8ES3L14	19'-11 1/2"
CB-6	5/8" DIA. ROD	24'-6"
CB-7	1/2" DIA. ROD	22'-8"

CONNECTION PLATES	
ROOF PLAN	
ID	MARK/PART
1	SC18



ROOF FRAMING PLAN

- GENERAL NOTES:**
- INSTALL ALL PURLIN AND FLANGE BRACES (FB) AS SHOWN.
  - ROOF PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
  - STRUT PURLINS, IF PROVIDED, MUST BE INSTALLED AND FASTENED TO ROOF SHEETING PER "PBR" PANEL ROOF DETAIL.
  - DO NOT ADD ANY ADDITIONAL ROOF OPENINGS WITHOUT BUILDING MANUFACTURER APPROVAL OR PROFESSIONAL ENGINEER APPROVAL.
  - DO NOT STACK SHEET BUNDLES ON ROOF. ONLY RAISE INDIVIDUAL SHEETS AS NEEDED.
  - AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV




Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 385-8001  
 Rocky Mount, NC. (252) 977-2131  
 www.cecobuildings.com

PROJECT: NATALIE DAVIDSON		OWNER: NATALIE DAVIDSON	
CUSTOMER: THE STEEL BUILDER			
LOCATION: SPARKS, NV 89441-8549 US			
CAD	DATE	SCALE	PHASE
	2/ 3/23	N.T.S.	1
BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
A	19-B-27926	E1	0



PBR ROOF SHEETING NOTE:  
 PBR ROOF PANELS ARE TO BE FIELD CUT IF THE PANELS EXTEND  
 OUTSIDE OF THE ROOF PLANE, PANELS ARE NOT TO BE BACK LAPPED.



NOTE: (8 QTY)  
 LTP'S TO BE FIELD LOCATED  
 & FIELD CUT (BY OTHERS)  
 INSTALLATION MUST COMPLY  
 WITH OSHA REQUIREMENTS

- 1) 8 QTY OF LTP'S ARE FIELD SEE DETAIL GPR25100/DET17
- 2) 1 QTY OF RIDGE VENT IS FIELD SEE DETAIL GPR13202/DET16

ROOF SHEETING PLAN  
 PANELS: 26 Gauge PBR - Galvalume

- GENERAL NOTES:
1. INSTALL ALL PURLIN AND FLANGE BRACES (FB) AS SHOWN.
  2. ROOF PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
  3. STRUT PURLINS, IF PROVIDED, MUST BE INSTALLED AND FASTENED TO ROOF SHEETING PER "PBR" PANEL ROOF DETAIL.
  4. DO NOT ADD ANY ADDITIONAL ROOF OPENINGS WITHOUT BUILDING MANUFACTURER APPROVAL OR PROFESSIONAL ENGINEER APPROVAL.
  5. DO NOT STACK SHEET BUNDLES ON ROOF. ONLY RAISE INDIVIDUAL SHEETS AS NEEDED.
  6. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV




Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 385-8001  
 Rocky Mount, NC. (252) 977-2131  
 www.cecobuildings.com

PROJECT: NATALIE DAVIDSON		OWNER: NATALIE DAVIDSON					
CUSTOMER: THE STEEL BUILDER							
LOCATION: SPARKS, NV 89441-8549 US							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	E2	0


Drawing has been digitally signed.



MEMBER TABLE		
FRAME LINE A		
MARK	PART	LENGTH
E-1	8ES3L14	19'-11 1/2"
E-2	8ES3L14	19'-11 1/2"
E-3	8ES3L14	19'-11 1/2"
G-12	8X25Z16	21'-5 1/2"
G-13	8X25Z16	22'-11 1/2"
G-14	8X25Z16	21'-5 1/2"
CB-5	3/4" DIA. ROD	25'-4"



SIDEWALL FRAMING: FRAME LINE A



SIDEWALL SHEETING & TRIM: FRAME LINE A

PANELS: 26 Gauge PBR - Polar White

- GENERAL NOTES:**
1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
  2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
  3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
  4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV



Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 385-8001  
 Rocky Mount, NC. (252) 977-2131  
 www.cecobuildings.com


PROJECT: NATALIE DAVIDSON		OWNER: NATALIE DAVIDSON					
CUSTOMER: THE STEEL BUILDER							
LOCATION: SPARKS, NV 89441-8549 US							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	E3	0




Drawing has been digitally signed.



MEMBER TABLE		
FRAME LINE E		
MARK	PART	LENGTH
E-2	8ES3L14	19'-11 1/2"
E-4	8ES3L14	19'-11 1/2"
E-5	8ES3L14	19'-11 1/2"
G-12	8X25Z16	21'-5 1/2"
G-13	8X25Z16	22'-11 1/2"
G-14	8X25Z16	21'-5 1/2"
CB-5	3/4" DIA. ROD	25'-4"



SIDEWALL FRAMING: FRAME LINE E



SIDEWALL SHEETING & TRIM: FRAME LINE E

PANELS: 26 Gauge PBR - Polar White

- GENERAL NOTES:**
1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
  2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
  3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
  4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV

Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 385-8001  
 Rocky Mount, NC. (252) 977-2131  
[www.cecobuildings.com](http://www.cecobuildings.com)

PROJECT: NATALIE DAVIDSON		OWNER: NATALIE DAVIDSON					
CUSTOMER: THE STEEL BUILDER							
LOCATION: SPARKS, NV 89441-8549 US							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	E4	0




**BEARING FRAME ONLY!**  
 WASHER TO BE USED AT ENDWALL COLUMN TO ENDWALL RAFTER CONNECTION. USE ONE WASHER ON COLUMN SIDE. WASHER NOT NEEDED ON CLIP SIDE.

BOLT TABLE FRAME LINE 1				
LOCATION	QUAN	TYPE	DIA	LENGTH
ER-1/ER-2 Columns/Raf	8	A325	5/8"	3/4"
	4	A325	1/2"	1 1/4"


MEMBER TABLE FRAME LINE 1		
MARK	PART	LENGTH
EC-1	8F35C13	14'-6 1/4"
EC-2	W8X10	18'-1 3/16"
EC-3	8F25C12	18'-1 3/16"
EC-4	8F25C14	14'-6 1/4"
ER-1	10F35C12	25'-9"
ER-2	10F35C12	25'-9"
DJ-1	8X35C14	14'-0"
JB-1	8X35C14	3'-0"
JB-2	8X35C14	2'-4"
G-1	8X25Z16	13'-7 3/4"
G-2	8X25Z16	2'-4 1/4"
G-3	8X35C14	19'-7 3/4"
G-4	8X25Z16	19'-7 3/4"
G-5	8X25Z16	2'-8"
CB-1	1/2" DIA. ROD	22'-8"
CB-2	1/2" DIA. ROD	20'-1"

FLANGE BRACE TABLE FRAME LINE 1		
MARK	ID	LENGTH
1	FB30	L2X2X1/8
2	FB6-1	L2X2X1/8

CONNECTION PLATES FRAME LINE 1	
ID	MARK/PART
1	SC5
2	CL751



ENDWALL FRAMING: FRAME LINE 1



ENDWALL SHEETING & TRIM: FRAME LINE 1

PANELS: 26 Gauge PBR - Polar White

REFER DETAIL CF02035 FOR SC90 PLATE

**GENERAL NOTES:**

1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV




Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 335-8001  
 Rocky Mount, NC. (252) 977-2131  
 www.cecobuildings.com


PROJECT: NATALIE DAVIDSON		OWNER: NATALIE DAVIDSON	
CUSTOMER: THE STEEL BUILDER			
LOCATION: SPARKS, NV 89441-8549 US			
CAD	DATE	SCALE	PHASE
	2/ 3/23	N.T.S.	1
BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
A	19-B-27926	E5	0

Drawing has been digitally signed.





ENDWALL FRAMING: FRAME LINE 5



ENDWALL SHEETING & TRIM: FRAME LINE 5

PANELS: 26 Gauge PBR - Polar White

REFER DETAIL CF02035 FOR SC90 PLATE

- GENERAL NOTES:**
1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
  2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
  3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
  4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

**BEARING FRAME ONLY!**  
 WASHER TO BE USED AT ENDWALL COLUMN TO ENDWALL RAFTER CONNECTION. USE ONE WASHER ON COLUMN SIDE. WASHER NOT NEEDED ON CLIP SIDE.

BOLT TABLE FRAME LINE 5				
LOCATION	QUAN	TYPE	DIA	LENGTH
ER-3/ER-4	8	A325	5/8"	2"
Cor_Column/Raf	4	A325	1/2"	1 1/4"
EC-6/ER-3	4	A325	5/8"	1 1/4"

MEMBER TABLE FRAME LINE 5		
MARK	PART	LENGTH
EC-5	12F25C14	14'-6 3/8"
EC-6	12F35C12	20'-4 3/4"
EC-7	12F35C14	14'-6 3/8"
ER-3	W10X12	25'-9"
ER-4	W10X12	25'-9"
G-6	8X35Z13	23'-7 3/4"
G-7	8X35Z14	23'-7 3/4"
G-8	8X25Z16	9'-1 3/4"
G-9	8X35Z13	23'-11 1/2"
G-10	8X35Z14	23'-11 1/2"
G-11	8X25Z16	9'-1 3/4"
CB-3	1/2" DIA. ROD	28'-4"
CB-4	1/2" DIA. ROD	31'-7"

FLANGE BRACE TABLE FRAME LINE 5			
MARK	∇ ID	PART	LENGTH
1	FB29.8	L2X2X1/4G	2'-5 3/4"
2	FB6-2	L2X2X1/8	2'-5 3/4"

CONNECTION PLATES FRAME LINE 5	
ID	MARK/PART
1	CLS49
2	SC5



Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 385-8001  
 Rocky Mount, NC. (252) 977-2131  
[www.cecobuildings.com](http://www.cecobuildings.com)

PROJECT: NATALIE DAVIDSON		OWNER: NATALIE DAVIDSON	
CUSTOMER: THE STEEL BUILDER			
LOCATION: SPARKS, NV 89441-8549 US			
CAD	DATE	SCALE	PHASE
	2/ 3/23	N.T.S.	1
BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
A	19-B-27926	E6	0




SPLICE PLATE & BOLT TABLE									
Mark	Qty Top	Qty Bot	Int	Type	Dia	Length	Width	Thick	Length
SP-1	4	4	2	A325	3/4"	2"	6"	1/2"	2'-7 5/8"
SP-2	4	4	0	A325	3/4"	1 3/4"	6"	3/8"	1'-7 1/8"

STIFFENER TABLE				
Mark	Stiff Mark	Width	Thick	Length
RF1-1	ST1	2 1/2	1/4"	26"

BASE PLATE TABLE				
Col Mark	Width	Thick	Length	Plate Size
BP-1	6"	3/8"	10 1/2"	

MEMBER TABLE						
Mark	Web Depth		Web Plate		Outside Flange	
	Start/End	Length	Thick	Length	W x Thk x Length	Inside Flange W x Thk x Length
RF1-1	10.0/26.0	0.134	191.5		5 x 1/4" x 184.9	5 x 1/4" x 164.2
RF1-2	24.0/12.0	0.134	98.3		5 x 1/4" x 35.5	5 x 1/4" x 240.0
	12.0/12.0	0.134	180.0		5 x 1/4" x 32.2	5 x 1/4" x 176.9

FLANGE BRACES: FBxx (1 or 2)  
 xx=length(in)  
 (1) One Side; (2) Two Sides  
 A - L2X2X1/4G  
 FB6 - L2X2X1/8



REFER DETAIL CF02035 FOR SC90 PLATE


RIGID FRAME ELEVATION: FRAME LINE 2 3 4




- GENERAL NOTES:
- BOLT TIGHTENING-BOLTED JOINTS WITH ASTM A325 TYPE 1 BOLTS GREATER THAN 1/2" DIAMETER ARE SPECIFIED AS PRETENSIONED JOINTS IN ACCORDANCE WITH THE MOST RECENT EDITION OF THE RCSC SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A449 BOLTS. PRETENSIONING CAN BE ACCOMPLISHED BY USING THE TURN-OF-NUT METHOD OF TIGHTENING, CALIBRATED WRENCH, TWIST-OFF-TYPE TENSION-CONTROL BOLTS OR DIRECT-TENSION-INDICATOR AS ACCEPTABLE TO THE INSPECTING AGENCY AND BUILDING OFFICIAL. INSTALLATION INSPECTION REQUIREMENTS FOR PRETENSIONED JOINTS (SPECIFICATION FOR STRUCTURAL JOINTS SECTION 9.2) USING TURN-OF-NUT METHOD IS SUGGESTED. THE CONNECTIONS ON THIS PROJECT ARE NOT SLIP CRITICAL.
  - ALL FIELD CONNECTIONS OF SECONDARY FRAMING SHALL BE BOLTED WITH A325 BOLTS.
  - INSTALL ALL FLANGE BRACES ON COLUMN AND RAFTER AS SHOWN.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV

Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 385-8001  
 Rocky Mount, NC. (252) 977-2131  
[www.cecobuildings.com](http://www.cecobuildings.com)

PROJECT: NATALIE DAVIDSON		OWNER: NATALIE DAVIDSON	
CUSTOMER: THE STEEL BUILDER			
LOCATION: SPARKS, NV 89441-8549 US			
CAD	DATE	SCALE	PHASE
	2/ 3/23	N.T.S.	1
BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
A	19-B-27926	E7	0





Page	CF02035
Date	Dec '14
Rev	04

A5	Purlin To Bearing Frame Single Cold Form Rafter	Date Jul '21
Page MB-A5		Rev 02

A7	Purlin To Bearing Frame Hot Rolled Rafter	Date Jul '21
Page MB-A7		Rev 02




ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV

**CECO Building Systems**  
 Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 385-8001  
 Rocky Mount, NC. (252) 977-2131  
 www.cecobuildings.com

PROJECT: NATALIE DAVIDSON  
 CUSTOMER: THE STEEL BUILDER  
 LOCATION: SPARKS, NV 89441-8549 US  
 OWNER: NATALIE DAVIDSON

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET1	0

Drawing has been digitally signed.



B4

Cold Form Endwall  
Column To Rafter

Date  
Aug '20

Rev  
01

B6

Hot Rolled Endwall  
Column To Rafter

Date  
Aug '20

Rev  
01

C4

Girt To Cold Form Column

Date  
Jun '17

Rev  
00

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV






Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 385-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com

PROJECT: NATALIE DAVIDSON		OWNER: NATALIE DAVIDSON					
CUSTOMER: THE STEEL BUILDER							
LOCATION: SPARKS, NV 89441-8549 US							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET2	0

Drawing has been digitally signed.





C6

Girt To Hot Rolled  
Endwall Column

Date  
Jun '17  
Rev  
00

C13

Page  
MB-C13

Girt To Cold Form Endwall  
Column - Partially Open

Date  
Jun '17  
Rev  
00

C15

Page  
MB-C15

Girt To Hot Rolled Endwall  
Column - Partially Open

Date  
Jun '17  
Rev  
00

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV






Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 385-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com

PROJECT: NATALIE DAVIDSON		OWNER: NATALIE DAVIDSON					
CUSTOMER: THE STEEL BUILDER							
LOCATION: SPARKS, NV 89441-8549 US							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET3	0



Drawing has been digitally signed.



D4	Girt To Cold Form Corner Column	Date Oct '19	E3
Page MB-D4		Rev 01	Page MB-E3

Endwall Column Base Plate	Date Dec '18	E5
	Rev 01	Page MB-E5


Door Jamb Base Plate	Date Dec '18
	Rev 01

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV





Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 385-8001  
 Rocky Mount, NC. (252) 977-2131  
 www.cecobuildings.com

PROJECT:	NATALIE DAVIDSON	OWNER:	NATALIE DAVIDSON				
CUSTOMER:	THE STEEL BUILDER						
LOCATION:	SPARKS, NV 89441-8549 US						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET4	0





Drawing has been digitally signed.





\* - Refer To Anchor Rod Setting Plan For Dimension



E8

Cold Form Endwall Column Base Plate

Date  
Dec '18  
Rev  
01

F10

Page  
MB-F10

Endwall Bearing Frame - Cold Form Rafter Splice At Ridge

Date  
Jun '17  
Rev  
00

F20B

Page  
MB-F20B

Endwall Bearing Frame - Cold Form Rafter Splice At Ridge

Date  
Jun '17  
Rev  
00

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SVX






Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 385-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com

PROJECT:	NATALIE DAVIDSON	OWNER:	NATALIE DAVIDSON				
CUSTOMER:	THE STEEL BUILDER						
LOCATION:	SPARKS, NV 89441-8549 US						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET5	0



Drawing has been digitally signed.



G2	Purlin To Rigid Frame	Date Sep '19	H2	Girt To Rigid Frame	Date Sep '19	I6	Low Side Eave Strut To Bearing Frame - Cold Form	Date Jun '17
Page MB-G2		Rev 01	Page MB-H2		Rev 01	Page MB-I6		Rev 00

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV






Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 385-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com

PROJECT:	NATALIE DAVIDSON						
CUSTOMER:	THE STEEL BUILDER	OWNER: NATALIE DAVIDSON					
LOCATION:	SPARKS, NV 89441-8549 US						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET6	0



Drawing has been digitally signed.



18

Low Side Eave Strut To Bearing Frame - Hot Rolled

Date Jun '17

J4

Eave Strut To By-Pass Rigid Frame At Interior

Date Jun '17

K3

Girt To Single Cold Form Jamb/Sub Jamb

Date Dec '17

Page MB-18

Rev 00 Page MB-J4

Rev 00 Page MB-K3

Rev 00

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SVX




Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 385-8001  
 Rocky Mount, NC. (252) 977-2131  
 www.cecobuildings.com



PROJECT:	NATALIE DAVIDSON	OWNER:	NATALIE DAVIDSON				
CUSTOMER:	THE STEEL BUILDER						
LOCATION:	SPARKS,NV 89441-8549 US						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET7	0



Drawing has been digitally signed.



\* Similar Connection at Rafter  
 \*\* Flat Washer WF500 Has A Larger Outside Diameter Than Flat Washer WFH500 And Is To Be Located Next To The Slope Washer



L8

Single Cold Form Jamb/  
Sub Jamb To Girt

Date  
Jun '17  
Rev  
00

Q3

Page  
MB-Q3

Rod Brace Attachment At Web

Date  
Mar '18  
Rev  
01

R2

Page  
MB-R2

Anchor Rods At Frame Column

Date  
Dec '17  
Rev  
00

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV






Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 385-8001  
 Rocky Mount, NC. (252) 977-2131  
 www.cecobuildings.com

PROJECT: NATALIE DAVIDSON  
 CUSTOMER: THE STEEL BUILDER OWNER: NATALIE DAVIDSON  
 LOCATION: SPARKS, NV 89441-8549 US  
 CAD DATE SCALE PHASE BUILDING ID JOB NUMBER SHEET NUMBER ISSUE  
 2/ 3/23 N.T.S. 1 A 19-B-27926 DET8 0



Drawing has been digitally signed.



U2		Bolts At Rigid Frame Ridge Rafter Connection		Date Jun '17	U3		Bolts At Rigid Frame Rafter To Column Connection		Date Jun '17	W10		Girt To Hot Rolled Endwall Rafter		Date May '19
Page MB-U2				Rev 00	Page MB-U3				Rev 00	Page MB-W10				Rev 00

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV



Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 385-8001  
 Rocky Mount, NC. (252) 977-2131  
 www.cecobuildings.com


PROJECT: NATALIE DAVIDSON		OWNER: NATALIE DAVIDSON					
CUSTOMER: THE STEEL BUILDER							
LOCATION: SPARKS, NV 89441-8549 US							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET9	0




Drawing has been digitally signed.

PBR Roof Panel  
Fastener And Tape Sealant Location

Page  
GPR00011  
Date  
Apr '19  
Rev  
01



All Roof Members Except As Noted Below




At Eave Strut, Panel End Lap And Peak Purlin

Note:  
Screw patterns shown satisfy U.L. 90 requirements for roof.


PBR Roof Panel  
Side Lap And End Lap Details

Page  
GPR04016  
Date  
Apr '19  
Rev  
04



Formed Base Trim Details

Page  
PW02010  
Date  
Feb '18  
Rev  
01




ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV





Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 385-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com

PROJECT:	NATALIE DAVIDSON						
CUSTOMER:	THE STEEL BUILDER			OWNER: NATALIE DAVIDSON			
LOCATION:	SPARKS, NV 89441-8549 US						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET10	0





Wall panel must be held off of base trim a minimum of 1/4\"/>



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV




Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 335-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com

PROJECT:	NATALIE DAVIDSON						
CUSTOMER:	THE STEEL BUILDER						
OWNER:	NATALIE DAVIDSON						
LOCATION:	SPARKS, NV 89441-8549 US						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET11	0




**PBR Roof Panel - Northern Standard And Northern Large  
Edgecraft Rake Trim - Sheeted Wall**

Page **TPR05006**  
Date **Jul '20** | Rev **00**




**PBR Roof Panel  
Peak Box At Fixed Ridge**

Page **GPR05001**  
Date **Jun '21** | Rev **08**



**Single Skin Wall Panel Outside Closure Requirements at Eave**

Page **GD06002**  
Date **Feb '19** | Rev **02**



Detail at Foam Closure  
(Low Eave Shown High Eave Similar)

Detail at Optional Metal Closure  
For PBR Panel Only  
(Low Eave Shown High Eave Similar)

**Note:**  
Foam Closures Are Required When Job Requires Air Infiltration Or Sealed Wall Requirements, See GD16002.

Wall Panel	Foam Closure
PBR	HW456
AVP	HW465
PBU	HW460
VistaShadow	HW465
NuWall	HW424
PBC	HW462
PBD	HW463
ShadowRib	HW412
Designer Series (Fluted-Only)	HW4037
RBR (Reverse Rolled PBR)	HW455
RBU (Reverse Rolled PBU)	HW459
7,2	HW461

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV






Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 385-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com

PROJECT:		NATALIE DAVIDSON							
CUSTOMER:			THE STEEL BUILDER			OWNER:		NATALIE DAVIDSON	
LOCATION: SPARKS, NV 89441-8549 US									
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE		
	2/3/23	N.T.S.	1	A	19-B-27926	DET12	0		







ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV

**CECO Building Systems**

Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 385-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com

PROJECT: NATALIE DAVIDSON  
CUSTOMER: THE STEEL BUILDER OWNER: NATALIE DAVIDSON  
LOCATION: SPARKS, NV 89441-8549 US

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET13	0

Drawing has been digitally signed.

Screw Application

Page TH06006X  
Date May '19 Rev 01

Standard Grade



Description	Fastener Number	Application
1/4"-14 x 7/8" Type 2	4A	Stitch & Trim Screw
12-14 x 1 1/4" Type 2	17A	Member Screw (Up To 4" Insulation)
12-14 x 1 1/2" Type 2	17B	Member Screw (Up To 6" Insulation)
12-14 x 2" Type 2	28	Member Screw

Long Life

Description	Fastener Number	Application
1/4"-14 x 7/8" Type 1	4	Stitch & Trim Screw
12-14 x 1 1/4" Type 2	3	Member Screw (Up To 4" Insulation)
12-14 x 1 1/2" Type 2	3A	Member Screw (Up To 6" Insulation)
12-14 x 2" Type 2	58	Member Screw


PBR Wall Panel  
Panel Side Lap

Page PW05002  
Date Mar '19 Rev 03



PBR Wall Panel  
Fastener Location

Page PW05003  
Date Aug '15 Rev 04



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SVX



Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 385-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com


PROJECT: NATALIE DAVIDSON		OWNER: NATALIE DAVIDSON					
CUSTOMER: THE STEEL BUILDER							
LOCATION: SPARKS, NV 89441-8549 US							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET14	0



**Light Transmitting Panel (LTP)  
PBR Roof Panel  
Standard Placement Guidelines**


Page: **GPR25102**  
Date: **Apr '17** Rev: **00**

\*Note: Roof Panel and Light Transmitting Panel to span a minimum of (2) purlin spaces.  
A minimum of 4" is required for panel endlaps. The non-insulated LTP may be field cut or endlap under the up-hill roof panel a maximum of 1'-0". Insulated LTP should not be cut in field.




**Trac-Rite Model 988 / 988WL & Model 977 / 977WL Roll-Up Door Mounting  
Plate Installation**

Page: **AC00835X**  
Date: \_\_\_\_\_ Rev: \_\_\_\_\_



**PBR Roof Panel - Northern Standard and Northern Large Edgecraft  
Low Eave Rake Corner with Flat Eave Trim -  $\frac{3}{4}$ " thru  $1\frac{3}{4}$ " Wall Panel**

Page: **TPR04009**  
Date: **Nov '20** Rev: **02**



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV



Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 335-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com


PROJECT: NATALIE DAVIDSON							
CUSTOMER: THE STEEL BUILDER			OWNER: NATALIE DAVIDSON				
LOCATION: SPARKS, NV 89441-8549 US							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/3/23	N.T.S.	1	A	19-B-27926	DET15	0

Drawing has been digitally signed.



**Notes:**


- Continuous Vents comes with a 10'-0" long chain pull factory attached for single vent damper operation and is field removed when vents are required to be linked together for continuous damper operation.
- Pull bars have a turnbuckle factory attached at one end and a bolt/nut assembly at the other end and are used to link the vents together for continuous damper operation.
- Refer to GPR13209 for optional Vent Operation.



**Vent Preparation Before Installation:**

The vent end caps are preformed for a 1:12 roof slope and require field modification to the end caps for roof slopes greater than 1:12 prior to installation. Field modification of the vent end cap is not required for roof slopes 1:12 and less.

Turn the ventilator cover and place the vent on it's top. There are five punch marks representing different roof slopes. Draw a line between the corners and to appropriate roof slope punch mark. Field cut and remove that portion of the end cap. See drawings below.







**End Skirt Installation:**






Position end skirt onto the vent end cap. Be sure the down-turned angle of the end skirt is positioned on the inside and tight against the vent end cap.

Attach the end skirt to the vent end cap with (6) Fastener #14. See drawing below.

Note: If vents are to be linked together for continuous damper operation only one end skirt installation is required.



**Isometric View HW401 Location at 12" Throat Continuous Vent**



Continuous Ridge Ventilator 9" or 12" Throat x 10'-0" Flat Base  
PBR Roof Panel Greater Than 2 1/2" 12 Roof Slope or With Expansion Ridge Trim

Proj	GPR13202
Date	Nov 17 01

**NOTE:** The Metal Building Manufacturer does not recommend the use of Ridge Ventilators on PBR roof systems on gable buildings over 200'-0" in width (100'-0" max. roof plane) or with roof slopes less than 1:12 or greater than 6:12.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV





Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 335-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com

PROJECT:	NATALIE DAVIDSON						
CUSTOMER:	THE STEEL BUILDER	OWNER: NATALIE DAVIDSON					
LOCATION:	SPARKS, NV 89441-8549 US						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/3/23	N.T.S.	1	A	19-B-27926	DET16	0



NOTE:  
If additional purlins occur  
between purlins shown in the  
isometric view add 9 Fastener  
#43L for each additional purlin






**GENERAL NOTES:**

- The light transmitting panels are not designed or intended to bear the weight of any person walking, stepping, standing, or resting on them. THE MANUFACTURER DISCLAIMS ANY WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, that any person can safely walk, step, stand, or rest on or near the light transmitting panels, or that they comply with any OSHA regulation. It is the Users responsibility to ensure that the installation and use of the light transmitting panels comply with State, Federal and OSHA regulations and laws, including, but not limited to, guarding all light transmitting panels with screens, fixed standard railings, or other acceptable safety controls that prevent fall-through.
- Non-insulated light transmitting panels may need to be cut in the field, if required, follow these steps: Up to five (5) LTP's may be cut at one time. A circular saw with a 24 tooth per inch blade, will work best. Cut slow and draw the blade to work without excess pressure. Allow the blade to cool between cuts.
- It is suggested to pre-drill the light transmitting panels before installing fasteners. This will help prevent fractures which may cause possible leaks.
- Remove drill shavings and metal filings from the surface of the panels at the end of each work day. Rust caused by these items can destroy the panel finish and void warranties.


**INSTALLATION NOTES:**

- Install roof panel and insulation according to standard procedures up to the desired location of the LTP shown on the "ROOF SHEETING PLAN". Install the LTP Flashing F75 at both sides of the LTP opening. Apply double face tape (not provided by Metal Bldg. Mfg.) to the sides of the LTP Flashing F75 to secure the insulation see Sections A and B.
- Install insulation above and below the LTP opening. Apply double face tape to the purlins to secure the insulation see Sections C and D.
- Apply Tape Sealer HWS07 at the panel sidlap as shown in Section A and the isometric view.
- Apply Tape Sealer HWS04 on top of the lower roof panel endlap (panel 2) and extend Tape Sealer HWS07 6" over the top of the roof panel sidlap Tape Sealer HWS07. See Section C and the isometric view.
- Apply Tape Sealer HWS07 on top of the LTP sidlap and Tape Sealer HWS04 at upper endlap. Extend Tape Sealer HWS07 6" over the top of the lower roof panel sidlap Tape Sealer HWS07 and the upper roof panel endlap (panel 3). See section d and the isometric view.
- Attach LTP panel at sidlaps with sidlap fastener at 10" o.c. and endlaps and purlins as shown in "Endlap and Purlin Fastener Layout".

**PBR Light Transmitting Panel Assembly Parts**  
UL 90 Rated Roof Construction Number 542



**Standard LTP Location**  
See GPR25102 for Standard Placement Guidelines



**CAUTION:**  
The following are examples of conditions that may cause condensation on Light Transmitting Panels  
(A) Projects where outside winter temperatures below 40° F are anticipated and where average winter interior relative humidity of 45% or greater is expected.  
(B) Building spaces with high humidity interiors, such as indoor swimming pools, textile manufacturing operations, food, paper or other wet process industrial plants.  
(C) Construction elements that may release moisture after the roof is installed, such as interior concrete and masonry, plaster finishes, and fuel burning heaters. The Building Manufacturer is not responsible for determining if condensation will be an issue on any particular application.

Non-Insulated PBR Light Transmitting Panel (LTP)  
Non UL 90 Application or UL 90 Application

Page: GPR25100  
Rev: Feb '20 '02

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV



Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 385-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com

PROJECT:	NATALIE DAVIDSON						
CUSTOMER:	THE STEEL BUILDER	OWNER: NATALIE DAVIDSON					
LOCATION:	SPARKS, NV 89441-8549 US						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET17	0




Drawing has been digitally signed.

PBR Wall Panel - Three Sided Framed Opening - Trim Installation with Field Notch Panel at Head Trim

Page PW07022  
Date Mar '20 Rev 05

Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.




Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Field measure Opening Width and Height before making field cuts and adjust cut dimensions accordingly.

PBR Wall Panel - Three Sided Framed Opening Field Notch Panel at Head Trim

Page PW07023  
Date Mar '20 Rev 05

Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.




Note: All trim is to be installed BEFORE blanket insulation is applied to walls

Note: Panel position is shown with Panel Rib and Opening on 1'-0 module. Location of Rib may vary depending on the Opening Width and location. Field measure before cutting Panel and Trim.

PBR Wall Panel - Three Sided Framed Opening - Trim Installation with Field Notch and Bend Tabs at Head Trim

Page PW07024  
Date Mar '20 Rev 05

Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Field measure Opening Width and Height before making field cuts and adjust cut dimensions accordingly.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV



Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 335-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com

PROJECT: NATALIE DAVIDSON  
CUSTOMER: THE STEEL BUILDER OWNER: NATALIE DAVIDSON  
LOCATION: SPARKS, NV 89441-8549 US




CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET18	0



**PBR Wall Panel - Three Sided Framed Opening - Field Notch and Bend Tabs at Head Trim**

Page PW07025  
Date Mar '20 Rev 05

Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.





Note: All trim is to be installed BEFORE blanket insulation is applied to walls

Note: Panel position is shown with Panel Rib and Opening on 1'-0" module. Location of Rib may vary depending on the Opening Width and location. Field measure before cutting Panel and Trim.

**PBR Wall Panel - Three Sided Framed Opening Jamb Trim Field Cut Details**

Page PW07027  
Date Mar '20 Rev 04





Note: Field measure Opening Height before making field cuts and adjust cut dimensions accordingly.

Jamb Trim F482 and Alternate Jamb Trim F484  
Front View  
Right Jamb Trim as shown  
Left Jamb Trim opposite hand

**PBR Wall Panel - Three Sided Framed Opening "Optional" Channel Closure Trim**

Page PW07028  
Date May '19 Rev 04



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV



Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 385-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com


PROJECT: NATALIE DAVIDSON  
CUSTOMER: THE STEEL BUILDER  
LOCATION: SPARKS, NV 89441-8549 US  
OWNER: NATALIE DAVIDSON

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET19	0



PBR Wall Panel - Three Sided Framed Opening - Jamb Trim Installation


Page PW07029  
Date Mar '20 Rev 05



Note: Terminate Blanket Insulation at Jamb Trim

Field flatten Trim leg when required

Jamb Trim F482 (shown) or Alternate Jamb Trim F484




Alternate Jamb Trim F484 Profile

Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Panel position is shown with Panel Rib and Opening on 1'-0" module. Location of Rib may vary depending on the Opening Width and location. Field measure before cutting Panel and Trim.

PBR Wall Panel - Three Sided Framed Opening Head Trim Installation

Page PW07030  
Date Oct '19 Rev 03



Opening Height + 3/4"  
Opening Height

Finish Floor

SL


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV



Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 335-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com

PROJECT: NATALIE DAVIDSON		OWNER: NATALIE DAVIDSON					
CUSTOMER: THE STEEL BUILDER							
LOCATION: SPARKS, NV 89441-8549 US							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET20	0

Drawing has been digitally signed.






PBR Wall Panel - Walk Door & Glass-Front Walk Door - Trim Installation with Field Notch Panel at Head Trim

Page PW09022  
Date Mar '20 Rev 03

Note: Trim Installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.




Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Field measure Door Width and Height before making field cuts and adjust cut dimensions accordingly.

PBR Wall Panel - Walk Door And Glass-Front Walk Door Field Notch Panel at Head Trim

Page PW09023  
Date Mar '20 Rev 02

Note: Trim Installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.




Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Panel position is shown with Panel Rib and Door on 1'-0" module. Location of Rib may vary depending on the Door Width and location. Field measure before cutting Panel and Trim.

PBR Wall Panel - Walk Door & Glass-Front Walk Door - Trim Installation with Field Notch and Bend Tabs at Head Trim

Page PW09024  
Date Mar '20 Rev 03

Note: Trim Installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Field measure Door Width and Height before making field cuts and adjust cut dimensions accordingly.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV



Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 385-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com


PROJECT:	NATALIE DAVIDSON						
CUSTOMER:	THE STEEL BUILDER	OWNER: NATALIE DAVIDSON					
LOCATION:	SPARKS, NV 89441-8549 US						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET21	0



PBR Wall Panel - Walk Door And Glass-Front Walk Door - Field Notch and Bend Tabs at Head Trim


Page PW09025  
Date Mar '20 Rev 02

Note: Trim installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.




PBR Wall Panel - Walk Door And Glass-Front Walk Door Jamb Trim Field Cut Details

Page PW09027  
Date Mar '20 Rev 03



PBR Wall Panel - Knock Down Door Jamb Trim Installation

Page PW09031  
Date Mar '20 Rev 07



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV



Columbus, MS. (662) 328-6722  
Mount Pleasant, IA. (319) 335-8001  
Rocky Mount, NC. (252) 977-2131  
www.cecobuildings.com


PROJECT: NATALIE DAVIDSON  
CUSTOMER: THE STEEL BUILDER  
LOCATION: SPARKS, NV 89441-8549 US  
OWNER: NATALIE DAVIDSON

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET22	0



PBR Wall Panel - Knock Down Walk Door - Head Trim Installation

Page PW09032  
 Date May '19 Rev 03



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/ 3/23	FOR ERECTOR INSTALLATION	IES	IES	SKV




Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 385-8001  
 Rocky Mount, NC. (252) 977-2131  
 www.cecobuildings.com


PROJECT: NATALIE DAVIDSON		OWNER: NATALIE DAVIDSON					
CUSTOMER: THE STEEL BUILDER							
LOCATION: SPARKS, NV 89441-8549 US							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/ 3/23	N.T.S.	1	A	19-B-27926	DET23	0




Drawing has been digitally signed.




Door Elevation




Walk Door Clip/Strike Reinforcement Angle Isometric




Door Jamb Extension Isometric



Knock Down Door Anchor Placement



Section A



Section B

Section C

The Adequacy Of The 2" Base Anchor Is Not The Responsibility Of The Building Manufacturer. The Adequacy Of These Base Anchors Should Be Determined By A Qualified Foundation Engineer.

Verify Door Jamb Base Clip Dimensions With Patterns Shown Prior To Placement Of Door Anchors And Adjust Patterns If Needed.

Note: 12 1/2" Frames May Not Have Kerf Door Frame Feature Depending On Door Manufacturer.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/3/23	FOR ERECTOR INSTALLATION	IES	IES	SVV



Columbus, MS. (662) 328-6722  
 Mount Pleasant, IA. (319) 335-8001  
 Rocky Mount, NC. (252) 977-2131  
 www.cecobuildings.com

PROJECT: NATALIE DAVIDSON		OWNER: NATALIE DAVIDSON					
CUSTOMER: THE STEEL BUILDER							
LOCATION: SPARKS, NV 89441-8549 US							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/3/23	N.T.S.	1	A	19-B-27926	DET24	0

Drawing has been digitally signed.




Knock Down Door - Girt At 7'-6" Without Low Girt

Page AC05200  
 Date Nov '18 Rev 00




**Building Anchorage**

- To Determine That The Foundation Is Square, Measure Diagonal Dimensions To Be Sure They Are Of Equal Length.
- To Determine That The Foundation Is Level, Set Up A Transit Or Level And Use A Level Rod To Obtain The Elevation At All Columns.
- Carefully Check The Location Of All Anchor Rods Against The Anchor Rod Setting Plan Furnished By The Manufacturer. All Dimensions Must Be Identical To Assure A Proper Start-up.



It Is Extremely Important That Anchor Rods Are Placed Accurately And In Accordance With The Anchor Rod Setting Plan. All Anchor Rods Should Be Held In Place With A Template Or Similar Means, So That They Will Remain Plumb And In Correct Location During The Placement Of The Concrete. A Final Check Should Be Made After Completion Of The Concrete Work And Prior To The Steel Installation. This Will Allow Necessary Corrections To Be Made Before Costly Installation Labor And Equipment Arrives.




**Pre-Erection Notes:**

The Following Notes, Procedures And Suggested Recommendations Are Important Parts Of The Pre-Erection Process.

- Prior To The Time The Erection Crew Arrives, A Responsible Person Should Check The Job Site For Foundation Readiness, Squares, And Accuracy And Anchor Rod Size And Location.

The Drawing Shown Below Indicates A Method Which May Be Used To Check The Foundation And Bolts For Square.




Measure Along Adjacent Sides Of Foundation Using A Pair Of Dimensions Shown. If The Diagonal Distance Between These Points Is As Noted, The Corner Is Square. Diagonal Measurements Between Opposite Anchor Rods Will Indicate If These Bolts Are Set Square.

**AISC Code Of Standard Practice For Steel Building And Bridges Tolerances For Setting Anchor Rods**

Anchor Rod Diameter, Inches (mm) \*Horizontal Variation, Inches (mm)

1/2" and 3/4" (19 And 22 mm)	1/2" (6 mm)
1", 1 1/4", 1 1/2" (25, 31, 38 mm)	3/4" (10 mm)
1 3/4", 2", 2 1/4" (44, 50, 63 mm)	1" (13 mm)



\* Horizontal Variations Vary Depending On Anchor Rod Diameter. See Above


**ANCHOR ROD SETTING TOLERANCES**

**Erection Tolerances**


**ERECTOR BRACING:**

It Is The Responsibility Of The Erector To Determine, Furnish And Install All Temporary Supports Such As Temporary Guys, Beams, Falsework, Crabbing, Or Other Elements Required For The Erection Operation (In Accordance With Section 7.10.3 Of ANS/AISC 303, Code Of Standard Practice For Steel Building And Bridges).


**COLUMN ALIGNMENT TOLERANCES**



**ALIGNMENT TOLERANCE FOR MEMBERS WITH FIELD SPICES**



**MEZZANINE BEAM HEIGHT TOLERANCE**



**General Erection Notes**


- All Structural Framing Members, Purins, Girts, Clips, Flange Braces, Bolts, Bracing Systems, Roof And Wall Panels, Etc. Must Be Installed As Shown On Erection Drawings.

- It Is Extremely Important, Especially During Construction, That Panels At The Eaves, Rakes And Ridges Be Kept Secure.

**Panel Cautions And Notes**

To Minimize Potential Of Corrosive Action At The Bottom Edge Of Wall Panels, The Contractor Must Assure That The Following Procedures Are Followed:

- The Concrete Foundation Should Be Cured For A Minimum Of Seven (7) Days Before Wall Panels Are Installed. (Uncured Concrete Is Highly Alkaline And Metal Panels Can Undergo Varying Degrees Of Corrosive Attack When In Direct Contact With The Concrete.) After The First Week Of The Curing Cycle, The Reaction Between Metallic Coatings On Steel And The Concrete Is Essentially Halted.
- Top Of Finish Grade At Building To Be A Minimum Of Four (4) Inches Below Bottom Of Panel.
- Finish Grade Is To Slope Away From Building To Ensure Proper Drainage.
- Upon Completion Of Finish Grading, All Dirt Is To Be Cleaned From Around Base Of Wall Panel Where It May Have Collected In Panel Notch Or On Base Trim.



**Fastener Installation**

Correct Fastener Installation Is One Of The Most Critical Steps When Installing Roof/Wall Panels. Drive The Fastener In Until It Is Tight And The Washer Is Firmly Seated. Do Not Overdrive Fasteners. A Slight Extrusion Of Neoprene Around The Washer Is A Good Visual Tightness Check. Always Use The Proper Tool To Install Fasteners. A Fastener Driver (Screw Gun) With A RPM Of 1700-2000 Should Be Used For Self-Drilling Screws. A 500-600 RPM Fastener Driver Should Be Used For Self-Tapping Screws. Discard Work Sockets, These Can Cause The Fastener To Wobble During Installation.

Note: Always Remove Metal Filings From Surface Of Panels At The End Of Each Work Period. Rusting Filings Can Destroy The Paint Finish And Void Any Warranty.



**Tape And Tube Sealant**

Proper Tape And Tube Sealant Application Is Critical To The Weather Tightness Of A Building. Tape Sealant Should Not Be Stretched When Installed. Apply Only To Clean, Dry Surfaces. Keep Only Enough Sealants On The Roof That Can Be Installed In A Day During Warm Weather. Store Sealants In A Cool Dry Place. During Cold Weather (Below 60°) Sealants Must Be Kept Warm (60°-90°) Until Application. After Tape Sealant Has Been Applied, Keep Protective Paper In Place Until Panel Is Ready To Be Installed.

**Important Note**

All Details, Recommendations And Suggestions Contained In This Erection Guide Of This Drawings Set Are For General Guidelines Only, And Not Meant To Be All-inclusive. Industry Accepted Installation Practices With Regard To All Areas Not Specifically Discussed In This Section Should Be Followed. Only Experienced, Knowledgeable Installers Familiar With Accepted Practices Should Be Used To Assure A Quality Project.


It Is Emphasized That The Manufacturer Is Only A Manufacturer Of Metal Building Components And Is Not Engaged In The Installation Of Its Products. Opinions Expressed By The Manufacturer About Installation Practices Noted In The Erection Guide Are Intended To Represent Only A Guide. Both The Quality And Safety Of Installation And The Ultimate Customer Satisfaction With The Completed Building Are Determined By The Experience, Expertise, And Skills Of The Installation Crews, As Well As The Equipment Available For Handling The Materials. Actual Installation Operations, Techniques And Site Conditions Are Beyond The Manufacturers Control.

Drawing has been digitally signed.



**PBR Roof Panels**

For PBR Roofs With Ridge Panels, It Is Recommended That Both Sides Of The Ridge Be Sheeted Simultaneously. This Will Keep The Insulation Covered For The Maximum Amount Of Time And The Panel Ribs Can Be Kept In Proper Alignment For The Ridge Panel. This Is Critical On The PBR Panels So That The Ridge Caps Can Be Properly Installed. Check For Proper Coverage As The Sheeting Progresses. In Certain Climate Regions



Install The First Run Of Roof Panels Across The Building From Eave To Eave Or Eave To Ridge, To Allow Proper Installation Of The Rake Trim, The Starting Location For The First Panel Must Be As Shown In The Rake Details Included With The Erection Drawings. When The First Run Is Properly Located And Aligned With The Correct Endgaps And Eave Overhangs, Fasten To Purlins. Roof Panels Should Be Installed So That The Sidewall Is In A Direction Away From Prevailing Wind. Refer To Appropriate Lap Details Included With The Erection Drawings.

Install Remaining Roof Insulation And Panels. To Avoid Accumulative Error Due To Panel Coverage Gain Or Loss, Properly Align Each Panel Before It Is Fastened. Occasional Checks Should Be Made To Ensure That Correct Panel Coverage Is Maintained. Special Attention Should Be Given To Fastener, Sealer and Closure Requirements. Refer To Details Included With The Erection Drawings.

At Finishing End Of Roof, The Last panels may Require Field Modification For Installation Of Rake Trim. Refer To Rake Details Included With The Erection Drawings. DO NOT BACK LAP THROUGH FASTENED ROOF PANELS.

**NOTE:** Roof Types And Installation Requirements Will Vary. Refer To The Appropriate Details For Specific Panel Uses.

**IMPORTANT:** Loose Fasteners, Blind Rivets, Drill shavings, Etc., Must Be Removed From The Roof To Guard Against Corrosion.


**Wall Panels**

Proper Horizontal And Vertical Alignment Of Supporting Structure (Girts Or Other Framing) Is The Responsibility Of The Installer. Failure To Align The Secondary members Properly Prior To Wall Installation Can Have A Direct Impact On The Final Appearance And Performance Of The Installed Wall System For Which The Metal Building Manufacturer Is Not Responsible.


Before Installing Wall Panels, The Girts Must Be Aligned To A Level Position So That There Is No Visible Sag. This Should Be Done Directly Ahead Of Panel Installation.

Girt Leveling May Be Accomplished By Standing A Section Of Cable Angle Vertically Against The Outside Girt Flanges At Approximate Mid-Bay Location. When Girts Are Level, Attach The Girt Flanges To The Angle With Vise Grip Pliers Or Temporary Screws. Wood Blocking Cut To Fit The Spaces May Also Be Used For Alignment.

**Note:** Temporary Girt Blocking Is Not Recommended On Concealed Fastener Panels. The Removal Of The Blocks After Panel Installation Can Cause Oil Canning.




**Note:** Wall Panel Type And Installation Details Will Vary. Refer To The Erection Drawings And Details For The Specific Panel Used For Your Building.



If Walls Are To Be Insulated With Blanket Insulation Over Girt Girt Flanges, Base And Eave, Place A Continuous Run Of Contact Tape Along The Eave Strut And Base Member.

**Note:** At The Base, Cut Off The Insulation A Minimum Of 2" Above The Bottom Of The Wall Panel. This Will Prevent The Insulation From Hanging Below The Wall Panel And Wicking Moisture.

**Note:** Additional Insulation May Be Required To Fill The Eave Strut And Prevent Condensation In Certain Climate Regions




**Eave Detail**  
(See Erection Drawings)



**Base Detail**  
(See Erection Drawings)


Sidewall Panels Should Be Installed So That The Panel Sidewall Is In A Direction Away From The Prevailing Wind. Refer To Appropriate Lap Detail Included With Erection Drawings.

**Note:** Check Periodically To Ensure That All Panels Are Aligned And Plumb.




**Note:** After Drilling Panels, It Is Important To Clean Metal Filings Off All Panel Surfaces, Including Between Panels That Are Not Installed That Day, To Avoid Rust Stains.

**Suggested Method Of Purlin Attachment For Building Accessories**



\* Denotes Material Not Provided By Metal Building Manufacturer.  
The Total Hanger Load Shall Not Exceed The Design Collateral Load For The Building. Example: 5'-0" (Purlin Spacing) X 5'-0" (Hanger Spacing) X 6 PSF (collateral Load) = 150 Lbs.  
See Cover Sheet For Design Collateral Load For This Building.  
Note: If The Building Is Designed For 0 PSF Collateral Load, Then Adding Any Suspended System (I.e. Duct Work, Piping, Lights, Ceilings, Etc.) Will Correspondingly Reduce The Design Live Load.

**Roof Curbs When Not Supplied By Building Manufacturer**




The Curb Details Shown Illustrate The Building Manufacturers Recommended Curb Style And Installation Method. It Is The Erector/Installer's Responsibility To Provide The Proper Curb Style And Install Them In Accordance With The Procedures Established By These Details. Failure By The Erector/Installer To Follow These Recommendations May Result In The Curbs Damaging The Roof System Or Excluded From Warranties.

1. 0.080 Aluminum Or 18 Ga. Stainless Steel (No Galvalume® Or Galvanized).
2. Panel Rib To Panel Rib (No Flat Skirt Or Lay-Over Curbs).
3. Installed With Down Hill End Over Panel And Up Hill End Under Panel Application For Water Flow At Panel Splice.
4. Up Lift Prevention For Clip Applied Roof Systems Are Required If:
  - a. Wind Loads Exceed 110 MPH.
  - b. Curb Base Crosses A Purlin.
5. Supported on (4) Sides By Primary Or Secondary Framing.
6. Maximum Single Curb Weight Recommended Is 1500 Lbs.


**Roof Jack Installation when Not Supplied By Building Manufacturer**

**General Installation Notes**

- 1. Do Not Use Galvanized Roof Jacks, Lead Hats, Or Other Residential Grade Roof Jacks. These Roof Jacks Do Not Have 20 Year Service Life And In Case Of Lead Hats Will Cause Galvanic Corrosion Of The Roof Panel.
- 2. Use EPDM Rubber Roof Jacks With An Integral Aluminum Band Bonded Into The Perimeter Of The Base. EPDM Roof Jacks Have A Temperature Range From -65F To 212F. Use Silicone Roof Jacks For High Temperatures. Silicone Roof Jacks Have A Temperature Range Of -100F To 437F.
- 3. Retrofit Roof Jacks Are Available For Applications In Which The Top Of The Pipe Is Inaccessible, Eliminating The Possibility Of Sliding The Roof Jack Over The Top Of The Pipe.
- 4. Do Not Use Tube Sealant To Seal The Roof Jack To The Roof Panels. Use Roll Tape Sealer Between The Roof Jack And The Roof Panel And Attach The Roof Jack To The Roof Panel With Fastener #4 - 1/4 x 2" LL SD W/Washer At 1' O.C. Around The Base Of The Roof Jack. See Table Below For Quantities.
- 5. Trim The Top Of The Roof Jack To Fit Over The Pipe, Roll Down The Roof Jack Over The Pipe And Apply Tape Sealer For The Perimeter Of The Roof Jack Base Between The Roof Jack And The Roof Panel. Apply Tape Sealer Around The Pipe And Install A Stainless Steel Clamp (Not By Bldg. Mfr.) Over The Top Of The Roof Jack And Firmly Tighten To Form A Secure Compression Seal.
- 6. If The Pipe Diameter Is So Large To Block The Flow Of Water Down The Roof Panel, A Flat Base Roof Curb Must Be Installed Into The Roof And The Roof Jack Will Be Sealed To The Curb. A Two Piece Curb May Be Required When The Top Of The Pipe Is Inaccessible.
- 7. In Northern Climates, The Pipe Penetration Should Be Protected From Moving Ice Or Snow With A Snow Retention System Immediately Up Slope From The Pipe.



Install Pipe In Center To Allow Base Of Roof Jack To Lay Flat on Panel. Cannot Encompass More Than 75% Of Panel.



Drawing has been digitally signed.

